

or *Abstract*

INTRODUCTION

Finally, the particles will be accelerated to 10.7 MeV/u also by the SSC facility. Figure 1 shows the layout of the front end section of the SSC-Linac.

Parameters	Values
Design ion	$^{238}\text{U}^{34+}$
ECR ion source	
Extraction voltage	25 kV
Max. axial injection field	2.3 T
Frequency	18 GHz
RFQ Type	4-rod
Input /Output energy	3.73/143 keV /u
Inter-electrode voltage	70 kV
Max.current	200.0 μA
IH-DTLs	
Input /Output energy	0.143/1.025 MeV/u

The high charge state room temperature ECR ion source had been successfully constructed. This source magnet coils were cooled through evaporative cooling technology. The maximum mirror field was 2.3 T (with iron plug) and the effective plasma chamber volume was $\varnothing 76 \text{ mm} \times 260 \text{ mm}$. The commissioning test of ECR ion source had been performed continually from 2014. Various specie ion beams had been successfully delivered for the linac commissioning.

With 0.1 kW RF injection power and 11.92 kV extraction voltage, 200 μA of $^{16}\text{O}^{5+}$ was produced. The transverse emittances were measured by the emittance scanners located at the downstream of the analysing magnet. As shown in the Fig. 2, the measured normalized rms emittances at 200 μA beam current for $^{16}\text{O}^{5+}$ were 0.22 π mm.mrad and 0.15 π mm.mrad in horizontal and vertical plane, respectively.

†yinxj@impcas.ac.cn




Figure 2: Measured transverse emittances after analysing dipole magnet.

CW 4-ROD RFQ

The CW 4-rod RFQ had been developed under the successful cooperation between Peking University and IMP. Low level RF measurement of RFQ was carried out. The frequency of the cavity without tuning was 53.607 MHz, which was not far from the operation frequency of 53.667 MHz and can be easily tuned by the tuners. On the critical coupling state, the Q_0 value of the cavity was 6440, which was 97% of the design value. The electric field distribution along the bam line was measured adopting the conventional perturbation method. The error of the results had been analysed in details [2].

The high power conditioning took a few days from pulse mode to CW. After about 30 hours conditioning, 35 kW with 30% duty factor was fed into the cavity. After then, 35 kW in CW mode had been successfully carried out almost no feedback. The temperature of the cooling water increased from 15.1 °C to 20.4 °C while the RF power increased from 0 to 32 kW. And the maximum temperature occurred at the RF power coupler.

The first beam commissioning ($^{16}\text{O}^{5+}$, 149.5 μA) was successfully performed and ion was accelerated to 141.9 keV/u measured by the TOF method. After carefully RF conditioning, $^{40}\text{Ar}^{8+}$ ion beam was successfully accelerated, the measured energy and current were 142.8 keV/u and 198 μA , respectively. The transmission efficiency was 94%. The more detail had been reported in [3].

MEBT RE-BUNCHER

In the MEBT section of SSC-Linac, a spiral re-buncher with four gaps structure had been developed to implement the longitudinal matching between the RFQ and the DTL operating, as shown in Fig. 3. The design β and the shunt impedance were 0.0175 and 5812 k Ω , respectively. Due to the limited space, the cavity was designed as \varnothing 600 mm and 197 mm in length. The designed total power was 1.8 kW for the design ion and the corresponding gap voltage amplitude was 35 kV. The measured Q_0 was 3628 which was the 86.5% of the design value.

A fixed tuner and a movable tuner were employed for frequency compensated during the operation. It meant that the cavity was tuned to the working frequency by fixed tuner. After then the movable tuner was devoted into the normal operation.




Figure 3: Spiral re-buncher cavity.

The RF power was generated and feed into the bunch cavity by a commercial solid state RF power amplifier system including the LLRF system. The conditioning process was smooth without any interruption. It took about 40 hours from low RF power in the pulse mode shift to the full RF power in CW mode.

Figure 4 shows the bunch efficiency when the buncher turns on comparing it turns off. It can be found that the bunch efficiency is very efficient. The measured energy spread of bunched beam was $|\Delta W/W| \leq \pm 2\%$.




Figure 4: Measured bunch efficiency.

IH-DTLs

In the original design, the particle will be accelerated to 1.025 MeV/u by four IH-DTL cavities. However in the optimized design, the high energy section of the SSC-Linac adopted three IH-DTL cavities obtaining the same energy as origin design value. The first cavity DTL1(295 keV/u) had been installed and beam commissioning was successfully performed.

The second DTL had been finished in manufacture and is under the preparation of the RF measurement as shown in Fig. 5. The cavity body was made of steel ion with copper plated on the inner surface. The T-type stems and drift tubes were made of OFC. Water cooling channels were designed in the T-type stems which were housed in the tank wall.

The preliminary low level RF measurement for the DTL2 had been carried out using a network analyser in this May. The frequency response as a function of tuner

