

appreciable when arranging insertions for collisions. They will be suppressed locally with the help of correction systems placed inside each special insertion and designed with due account of its optics.

The basic parameters of stage I and II of the UNK are enlisted in Table.

Table 1
The Basic Characteristics of the UNK

Parameter	1st stage	2nd stage
Circumference, m	20771.8	20771.8
Maximum energy, GeV	600	3000
Injection energy, GeV	70	400-600
Critical energy, GeV	42	42
Maximum field, T	1	5
Injection field, T	0.116	0.67±1
Number of technological sections	2	2
Technological section length, m	800	800
Number of sections for colliding beams	4	4
Length of a section for colliding beams, m	490	490
Total number of dipoles	2176	2176
Total number of quadrupoles	454	438
Dipole length, m	5.8	5.8
Quadrupole length, m	3.7	3.7

The present IHEP 70 GeV accelerator (U-70) whose intensity is planned to be increased up to $5 \cdot 10^{13}$ ppp will be used as an injector. The UNK circumference is 14 times that of the U-70 which will enable stacking a proton beam of an intensity of $6 \cdot 10^{14}$ ppp. With such an intensity there could be attained a luminosity of $10^{32} \text{ cm}^{-2} \text{ sec}^{-1}$ in the colliding beam mode.

Fig. 3 shows the scheme of the UNK operation. An accelerated $5 \cdot 10^{13}$ ppp beam will be prebunched in the U-70 by an RF field at 200 MHz frequency equal to the UNK accelerating RF. Proton intensity will be stacked by 12 successive pulses injected from the U-70 into stage I of the UNK. A part of the UNK circumference is left unfilled by the beam which will make it possible to arrange time intervals between pulses necessary to ease the operation of the injection and extraction systems as well as to reduce particle losses. On stacking, the beam will be accelerated in stage I and transferred into stage II by one-turn injection. A cycle of stage II consists of 20 sec acceleration, 38 sec flat-top and 20 sec field fall. In the initial period of the UNK construction, from economic reasons, the field rise and fall time in the superconducting stage will be increased up to 40 sec.




Fig. 3. The magnetic cycle of the U-70 injector, of stage I and II of the UNK.

The layout of the basic constructions for the UNK is shown in fig. 4. To install the equipment for beam injection in both directions, 3.5 m in diameter tunnels are envisaged. Power supply and control systems for the technological equipment are installed in surface buildings connected with the underground tunnel by vertical shafts. In 12 buildings distributed uniformly over the UNK circumference (buildings 1/1-1/12) there will be positioned power supplies, computers for control and diagnostic systems, cooling systems, heat exchangers and ventilation systems. The cryogenic equipment will be put in the underground areas adjacent to each vertical shaft (fig. 4).




Fig. 4. The layout of the basic constructions of the UNK.

Building 1/13 is intended for installation of RF generators of the accelerating system. Building 1/14 will house power supplies for the injection and beam abort systems. Building 1/15 is designed for power supplies for the extraction systems in SS4.

2. SIMULATION OF THE UNK EQUIPMENT

Development of Superconducting Dipoles for the UNK

Work on development and study of a UNK full-scale superconducting dipole prototype is going on. A new series of 1-m dipoles has been developed, whose coils are manufactured from a wire with an improved current density. This allows to have a reserve in the critical current for the UNK working field under conditions of higher heat releases in the coil due to irradiation. This series of magnets, from the viewpoint of their construction, does not differ from those reported earlier^{4/}. The coils are manufactured from a keystone cable containing 24 strands, 0.85 mm in diameter. Each strand has 2970 Ni-Ti filaments, 10 μm in diameter, embedded into a copper matrix. The strands are coated with an alloy of Sn-5 wt % Ag.

In detail the results on tests of these magnets will be reported separately^{5/} at this conference. Fig. 5 illustrates the behaviour of magnets at high fields. It shows the training curves for one of the magnets in a pooling cryostat at various temperatures of the helium bath. The critical current reached the maximum value at each level after some quenches. The character of training does not change up to the fields close to 7 T. All the magnets of the new series are trained only in the fields going beyond the UNK working field which is 5 T. This testifies to a good mechanical rigidity of the magnets of the given construction and to their operational capability at 5 T.

This conclusion is also supported by the results of mechanical and magnetic measurements. Figs. 6 and 7 present the results of measuring harmonics of even and odd nonlinearities of inhomogeneous part of the magnetic field which is given in the form




Fig. 5. The training curves for magnets of DB series at various temperatures.





Fig. 6. Normal even nonlinearities of a dipole versus field level.






Fig. 10. The facility for testing full-scale magnets.




Fig. 11. The training curves for a full-scale magnet.

The construction of the first full-scale model has been chosen as the basis for further developments. Presently a full-scale dipole model is manufactured and assembled with a force-circulating cryostat and magnetic shield (fig. 12). It will be tested in the nearer future.



Fig. 12. Full-scale dipole with a force-circulating cryostat and magnetic shield.

Magnet of Stage I of the UNK

Stage I of the UNK will operate with conventional magnets. The dipole field varies from 0.116 T to 1 T. The dipoles are broken into two groups, 1084 dipoles in each, with a useful area of $70 \times 60 \text{ mm}^2$ (type A) and $91 \times 43 \text{ mm}^2$ (type B). Each dipole has an efficient length of 5800 mm. Besides, 8 dipoles of type B shortened to 1854 mm will be used to transfer a beam from one wall of the tunnel to the other.

Currently a full-scale dipole prototype of type A has been manufactured. Its general view is given in fig. 13. Fig. 14 shows the measured relative inhomogeneity of the vertical field component in the central cross-section for three field levels. Table 2 presents relative values of the multipole coefficients for the inhomogeneous part of the field at a distance of 35 mm from the centre. Skew multipoles have also been measured, their values are much less than $1 \cdot 10^{-4}$.




Fig. 13. The magnet of stage I of the UNK.




Fig. 14. The relative value of dipole field inhomogeneity.

The tolerable value of the field inhomogeneity is $2 \cdot 10^{-4}$. Therefore the prototype manufactured meets the required characteristics satisfactorily.

Accelerating System

Work on full-scale simulation of the UNK accelerating system^{6/} (see Table 3) is going on.

A test module of the accelerating system consisting of two cavities and wave-guide hybrid divider (see fig. 15) has been manufactured. The cavities have a

Table 2

Multipole Components of the Field
in the Central Dipole Cross-Section ($C_n \times 10^4$)

n	B_{y0}	0,1 T	0,5 T	1 T
2		-0,5	0,0	0,1
3		0,2	2,4	1,4
4		0,3	-0,3	0,2
5		1,1	0,5	0,6
6		0,1	-0,1	0,1
7		1,4	1,4	1,4
8		0,3	0,1	0,1
9		-1,8	-2,3	-2,3
10		0,2	0,3	0,2
11		2,1	1,9	1,9
12		0,4	0,3	0,3
13		-2,2	-2,8	-2,8




Fig. 15. An experimental module of the accelerating station.

built-in system to damp higher-order oscillations. The study performed shows that this damping system reduces the impedance of one module coupling with the beam to a tolerable level of 0.4 Ohm in a frequency range from 300 to 1500 MHz, with power losses not exceeding 3%. The cavities are also furnished with probe-type input power blocks, control coupling loops, and with tuning devices which allow to vary the cavity frequency by ± 100 MHz. The measured Q-factor of the cavities was $53 \cdot 10^3$ and the shunt impedance was 10 MOhm. The coupling between the cavities was 90 dB at the operating frequency and 30 dB between the adjacent arms of the hybrid. The cooling system for the cavity walls maintains their temperature constant to an accuracy of $\pm 1^\circ\text{C}$ in a quasistationary operating mode.

Table 3
Characteristics of the UNK Accelerating System

Parameter	1st stage	2nd stage
Acceleration time, sec	11	40
Total amplitude of RF voltage, MW	8	11
Maximum energy gain per turn, MeV	2.1	6
Maximum power transferred to beam, MW	3.4	9.6
Number of modules in the accelerating system	8	14
Maximum RF power supplied to a module, MW	0.8	0.8

During tests the cavities were RF-powered and the multipactor discharge was suppressed at the vacuum of $1 \cdot 10^{-6}$ Torr. A 250 kW output amplifier has been designed. Its tests are under way.

Vacuum System

In the colliding mode, the vacuum chambers of both stages of the UNK should have a vacuum not less than $2 \cdot 10^{-9}$ Torr. As reported earlier^{1/}, the vacuum chamber of the superconducting accelerator will be cooled by liquid nitrogen down to 77 K which will make it possible to remove heat releases in the chamber walls due to the induced current of a high-intensity beam. A study made on the cold chamber model showed that at this temperature no layers of gases form on the chamber surface, ion desorption is absent and the amount of gas released is very small^{2/}.

To visualize a possibility of obtaining the required vacuum in the chamber of the UNK stage I its full-scale section serviced by one pump has been tested. Influence of thermal treatment of the chamber prior to its assembling was studied. Electrochemical polishing of the chamber, baking in the furnace at 600°C as well as surface treatment at the initial stage of pumping down by an argon discharge with the total dose of $3 \cdot 10^{18}$ ions/cm² allow to reduce sufficiently the evacuation time. With a 100 l/sec ion pump and a sublimation pump with periodic evaporation of titanium a vacuum of $2 \cdot 10^{-9}$ Torr was attained in 900 hours at the first pumping down. During subsequent pumpings after filling with dry nitrogen a vacuum of $1.4 \cdot 10^{-9}$ Torr was attained within less than 100 hours.

The obtained results testify to a feasible opportunity to attain the required vacuum in stage I of the UNK without baking the vacuum chamber after its assembling.

3. PRESENT STATUS

Currently, the design of the UNK equipment, technological and power supply buildings and constructions are terminating. Simulation of the basic elements for the UNK is in progress. A station for beam recapture at a frequency of 200 MHz is under construction. Cryogenic equipment is being simulated and tested. For production of the UNK superconducting elements, IHEP is constructing a specialized workshop including automatized test facilities for their calibration.

Geological studies and work on choosing the optimal tunnel location with consideration for the actual geological slit are terminating. Construction of the southern part of the tunnel is being prepared, i.e. sites and access roads are being built. In the region of buildings 1/1 and 1/2 (fig. 4) first vertical shafts about 25 m deep have been built. Horizontal tunneling will be started in the nearer future.

REFERENCES

1. A.I. Ageyev, V.I. Balbekov, Yu.P. Dmitrevskiy et al, Proceedings of XI International Conference on High Energy Accelerators, Geneva, 1980, p. 60.
2. V.I. Balbekov, Yu.S. Fedotov, K.P. Myznikov et al, "The UNK Magnetic Structure", Report at VIII All-Union Conference on Charged Particle Accelerators, Serpukhov, 1982.
3. N.I. Andreyev, V.I. Balbekov, E.A. Bulatov et al, Preprint IHEP 82-31, Serpukhov, 1982.
4. V.I. Balbekov, E.A. Bulatov, V.I. Demyanchuk et al, IEEE Transactions on Magnetics, v. 1981, N5, p.1886.
5. N.I. Andreyev, V.I. Balbekov, E.A. Bulatov et al, "Development and Study of UNK Superconducting Dipole Models", Report at XII International Conference on High Energy Accelerators, FNAL, 1983.
6. V.V. Katalyov, S.S. Kovalyov, B.K. Shembel et al, "Development and Study of the UNK Accelerating System", All-Union Conference on Charged Particle Accelerators, Serpukhov, 1982.
7. Yu.G. Kalinin, V.G. Rogozinsky, V.L. Ushkov, Proceedings of VII All-Union Conference on Charged Particle Accelerators, Dubna, JINR, v. 1, p. 133.