

# FIRST RESULTS OF BEAM COMMISSIONING ON THE ESS SITE FOR THE ION SOURCE AND LOW ENERGY BEAM TRANSPORT

R. Miyamoto\*, R. Bebb, E. E. C. Bergman, I. Bergström, B. Bertrand, O. Buchan, H. Danared  
C. S. Derrez, E. M. Donegani, M. Eshraqi, T. Fay, B. Gålnander, V. Grishin, S. Haghtalab  
H. Hassanzadegan, R. Huber, A. Jansson, H. Kocevar, E. Laface, Y. Levinsen, J. E. Malkorra  
M. Mansouri, C. A. Martins, J. P. S. Martins, N. Milas, J. F. E. Müller, M. Muñoz, E. Nilsson  
L. Page, C. Plostinar, C. Rosati, L. Rosberg, T. Shea, A. G. Sosa, R. Tarkeshian, L. Tchelidze  
C. Thomas, F. Tidholm, E. Trachanas, P. van Velze, ESS, Lund, Sweden  
L. Celona, L. Neri, INFN-LNS, Catania, Italy

## Abstract

The European Spallation Source (ESS), currently under construction in Lund, Sweden, will be a spallation neutron source driven by a proton linac of an unprecedented 5 MW beam power. Such a high power requires its ion source (IS) to produce proton beam pulses at 14 Hz with a high peak current more than 62.5 mA and a long plateau up to 3 ms. The IS and the following low energy beam transport (LEBT) section were manufactured and tested with beam to meet ESS requirements at INFN-LNS and delivered to ESS towards the end of 2017. Beam commissioning of these two sections on the ESS site has started in September 2018 and will continue until the end of June 2019. This paper provides an overview on this first beam commissioning period at ESS and also presents results of IS characterization and testing on LEBT functionalities.

## INTRODUCTION

The proton linac of the European Spallation Source (ESS) has an unprecedented design beam power of 5 MW [1]. When the 5 MW beam is delivered to the target, the facility provides the brightest neutron source in the world. Such a high power requires production, efficient acceleration, and almost no-loss transport of a high current beam, thus making design and beam commissioning (BC) of this machine challenging. Table 1 summarizes high-level beam parameters of the ESS linac at the ion source (IS) and target.

The IS and following low energy beam transport (LEBT) were in-kind contributions from INFN-LNS and tested with beam at their site (*off-site BC*) [2–5]. BC of these two sections on the ESS site, which is the first stage of several BC stages [6–9], has started in September 2018 and continue until the end of June 2019. This paper provides an overview on statuses of the IS and LEBT systems during this BC and also reports results from characterization and tuning of the IS conducted at ESS. Results on characterization and tuning of the LEBT are covered in [10]. The paper also covers testing of the chopper system in the LEBT in the final part.

## IS AND LEBT SYSTEMS AND STATUS

This section provides an overview on the IS and LEBT systems and their statuses during this BC. The IS of ESS

Table 1: High-level Beam Parameters at IS and Target

Parameter	Units	IS	Target
Average power	kW	~0.5	5000
Kinetic energy	MeV	0.075	2000
Peak current (proton)	mA	~70	62.5
Peak current (total)	mA	~85	62.5
Pulse length	ms	~6	2.86
Pulse repetition rate	Hz	14	14
Duty cycle	%	~8	4

is a microwave discharge type, with the nominal extraction voltage of 75 kV. This type of source is known to produce a high current and high quality beam, and the off-site BC demonstrated production of a high quality proton beam with more than 70 mA out of the LEBT [3,4]. The confining field of the plasma chamber is produced by three coils (Fig. 1), and this provides great flexibility in turning. The three coils are referred to as Coil 1, 2, and 3, counting from the extraction side, in the following. During the BC, the IS initially suffered from grounding issues, which even caused damages to some electronics inside the 75 kV platform. This required consolidations against high-frequency discharges, in contrast to the situation of the off-site BC. Since completion of the consolidations in January 2019, the IS has established stable operation and provided as much as 174 hours of beam time in April 2019.

A schematics of the LEBT is shown in Fig. 1. The main components of the LEBT are two solenoids, which focus the diverging beam out of the IS and match it to the following radio frequency quadrupole (RFQ). Each solenoid also




Figure 1: Left: Schematics of IS chamber and extraction system. Right: Schematic of LEBT.

\* ryoichi.miyamoto@ess.se

houses dipole correctors (*steerers*) of each transverse plane. In-between the two solenoids, there is a tank (*Permanent Tank*) which houses diagnostics devices and the chopper. The chopper removes unnecessary head and tail parts of the pulse out of the IS, which is typically  $\sim 6$  ms, and transmit a pulse of the nominal  $\sim 3$  ms or a much shorter one, down to  $5 \mu\text{s}$ , for tuning purposes. In-between Solenoid 1 and Permanent Tank, there is an iris, which allows to adjust the beam current with its six movable blades, forming a hexagonal shape aperture. The iris is not available during this BC due to a motion control issue of its blades. It has to be tested and verified in the beginning of the next BC stage, prior to sending the beam to the RFQ. The minimum aperture radius in the LEBT is  $\sim 40$  mm up to the collimator at the end. The aperture of the collimator reduces to 7 mm at the interface to the RFQ. During this BC stage, an additional tank (*Commissioning Tank*) is placed right after the collimator, and this allows to house additional diagnostics devices and provide information of beam near the RFQ interface.

The LEBT houses five types of diagnostics devices, whose details are provided in [11]. For current measurement, there are two beam current monitors (BCMs) and one Faraday cup (FC). One of the BCMs measures the current in the cable from the high-voltage power supply to the platform, thus providing an indirect measurement of the IS current. Another BCM measures the current out of the collimator. The FC can be placed in either tanks. Beam induced fluorescence monitors (BIFMs) measure centroid position and profile of the beam. A pair for each plane has been installed and used in Permanent Tank, and another pair in Commissioning Tank is currently under deployment. One Allison scanner type emittance measurement unit (EMU) is housed in each tank, allowing to measure emittance at two locations. Doppler detector (Dpl), which measures fractions of ion species as well as their energies, are currently under deployment.

## IS CHARACTERIZATION AND TUNING

Characterization and tuning exercise of the IS have been repeated during this BC, despite thorough studies performed during the off-site BC [2, 4]. There is a chance that the IS may have to operate at off-nominal settings due a situation of the rest of the linac, and thus it is crucial to raise expertise at ESS and establish a systematic way to retune the IS.

Five main adjustable parameters of the IS are magnetron power, amount of  $\text{H}_2$  gas injection, and strengths of the three coils. It was found that there is an easy way to establish a local optimum setting of the IS in the space of these five parameters, mostly with just Coil 2. Figure 2 shows changes in beam pulse shapes during a scan of Coil 2, observed by the IS BCM (left) and FC in Permanent Tank (right). We can see that the IS current increased along with the Coil 2 strength. (If the Coil 2 strength had been increased further, the beam had no longer been extracted at some point due to loss of stability in plasma.) On the contrary, between 67 and 68 A of Coil 2 current, the current reaching to the FC saturates, and the pulse shape starts to show a drooping




Figure 2: Beam pulse changes during a Coil 2 scan. Magnetron power, Coil 1 current, Coil 3 current, and  $\text{H}_2$  injection were kept to 500 W, 120 A, 217 A, and 3.5 sccm.

effect. Clearly, this turnaround point give the local optimum setting in terms of both current and flatness. Increment of the  $\text{H}_2$  injection tends to raise the tail of the pulse, and thus allows to compensate the drooping effect. When fine-tuning the flatness, it is easier to select a Coil 2 value such as having slight drooping and then compensate it with the  $\text{H}_2$  injection.

The above mentioned simple scheme worked well over a large space of the five IS parameters. This allowed to establish many operation points and study global characteristics of the IS, in a prompt manner. For operation points established this way, Fig. 3 summarizes the relation between the IS current and the part reaching to the FC in Permanent Tank. Note that Solenoid 1 was kept to a fixed strength ( $-249$  mT), and the listed current is the mean over the 2.9 ms plateau towards the end of the pulse. As seen in the figure, the IS current is correlated with the magnetron power, as expected, but also depends a lot on coils settings. The current reaching to the FC in Permanent Tank is mostly determined by the initial divergence and fractions of ion species out the IS. The figure also indicates that these two factors are highly correlated to the resultant IS current alone.

## IS SETTINGS AND BEAM QUALITY

The previous section saw that many operation settings are possible for the IS of ESS. Out of many settings, two summarized in Table 2 have been most frequently tested; *Standard Setting* has a 87 mA IS current and *Low (Current) Setting* has 58 mA. Figure 4 shows the beam pulses for these two settings, observed by two BCMs and FC (in Commissioning




Figure 3: Currents at the IS and in Permanent Tank (from FC) for IS operation points. Solenoid 1, Steerer 1H, and Steerer 1V were kept to  $-249$  mT,  $-2.72$  mT, and  $-0.35$  mT.



## REFERENCES

- [1] R. Garoby *et al.*, “The European Spallation Source design”, *Phys. Scr.*, vol. 93, p. 014001, 2018.
- [2] L. Neri *et al.*, “Beam commissioning of the high intensity proton source developed at INFN-LNS for the European Spallation Source”, in *Proc. 8th Int. Particle Accelerator Conf. (IPAC’17)*, Copenhagen, Denmark, May 2017, paper WEOBB2, pp. 2530-2532.
- [3] Ø. Midttun, L. Celona, B. Cheymol, R. Miyamoto, L. Neri, and C. Thomas, “Measurements and simulations of the beam extraction from the ESS proton source”, in *Proc. 17th Int. Conf. on Ion Source*, Geneva, Switzerland, Oct. 2017, p. 080022.
- [4] Ø. Midttun, “Off-site commissioning report for the ESS proton source and LEBT”, ESS, Lund, Sweden, Rep. ESS-0190279, June 2018.
- [5] L. Celona *et al.*, “Ion source and low energy beam transport line final commissioning step and transfer from INFN to ESS”, in *Proc. 9th Int. Particle Accelerator Conf. (IPAC’18)*, Vancouver, Canada, April 2018, paper TUPML073, pp. 1712–1714.
- [6] R. Miyamoto, M. Eshraqi, and M. Muños, “ESS lianc plans for commissioning and initial operations”, in *Proc. 57th ICFA Advanced Beam Dynamics Workshop on High-Intensity and High-Brightness Hadron Beams (HB’16)*, Malmö, Sweden, July 2016, paper TUPM5Y01, pp. 342–347.
- [7] R. Miyamoto, M. Eshraqi, M. Muños, and C. Plostinar, “Beam commissioning planning updates for the ESS linac”, in *Proc. 8th Int. Particle Accel. Conf. (IPAC’17)*, Copenhagen, Denmark, May 2017, paper TUPVA131, pp. 2407–2410.
- [8] R. Miyamoto *et al.*, “Preparation towards the ESS linac ion source and LEBT beam commissioning on ESS site”, in *Proc. 9th Int. Particle Accelerator Conf. (IPAC’18)*, Vancouver, Canada, paper TUPAF064, pp. 874–877.
- [9] C. Plostinar *et al.*, “Opportunities and challenges in planning the installation, testing and commissioning of large accelerator facilities”, in *Proc. 9th Int. Particle Accelerator Conf. (IPAC’18)*, Vancouver, Canada, paper TUPAF065, pp. 878–881.
- [10] R. Miyamoto *et al.*, “ESS low energy beam transport tuning during the first beam commissioning stage”, presented at the 10th Int. Particle Accelerator Conf. (IPAC’19), Melbourne, Australia, May 2019, paper MOPTS084, this conference.
- [11] C. S. Derrez *et al.*, “Initial performance of the beam instrumentation for the ESS IS&LEBT”, presented at the 10th Int. Particle Accelerator Conf. (IPAC’19), Melbourne, Australia, May 2019, paper WEPGW076, this conference.
- [12] A. Caruso *et al.*, “Experimental performance of the chopper for the ESS linac”, in *Proc. 9th Int. Particle Accelerator Conf. (IPAC’18)*, Vancouver, Canada, paper TUPML071, pp. 1709–1711.